

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-115-20183 0000

LEASE NAME Louis

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

990 Ft. from N Section Line

660 Ft. from E Section Line

SEC. 19 TWP. 21 RGE. 5 (E) or (W)

COUNTY Marion

Date Well Completed 5-25-73

Plugging Commenced 4-16-86

Plugging Completed 4-17-86

LEASE OPERATOR Tiechgraeber Oil Operations

ADDRESS Box 471 El Dorado, Kansas 67042

PHONE# (316) 321-2770 OPERATORS LICENSE NO. 0601

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Mirlan Unruh

Is ACO-1 filed? If not, is well log attached? NA

Producing Formation Depth to Top Bottom T.D. 2370'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	<u>E 204'</u>			<u>10.75"</u>		
	<u>2369.5'</u>			<u>7"</u>		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mixed and dumped 7 sacks of cement and dump on rock bridge @ 2300'.
Set rock bridge @ 290' to 260'. 15 sacks of cement 6% gel from 260' to 150'.
150' to 20' gel spacer. 20' to surface w/5 sacks of cement.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Long Drilling Company License No. 6112


Address Box 131 Hamilton, Kansas 66853

STATE OF Kansas COUNTY OF Greenwood, ss.

Partner of Long Drilling Company (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Rt. 1 Box 58 Hamilton, Ks. 66853



SUBSCRIBED AND SWORN TO before me this 22nd day of April, 19 86

[Signature]
Notary Public

My Commission Expires: 3-10-90

RECEIVED
STATE CORPORATION COMMISSION

APR 24 1986

Form CP-4
Revised 08-84

CONSERVATION DIVISION
Wichita, Kansas