

LEASE NAME C. Curtis

WELL NUMBER D-2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

4290 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 15 TWP. 22 RGE. 12W (E) or (W)

LEASE OPERATOR Rupe Oil Company, Inc.

COUNTY Stafford

ADDRESS P.O. Box 783010 Wichita, Kansas 67278-3010

PHONE# (316) 689-3520 OPERATORS LICENSE NO. 5047

Date Well Completed _____

Character of Well Oil

Plugging Commenced 6-11-01

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-12-01

The plugging proposal was approved on _____ (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3665'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	251'	None
				5-1/2"	3664'	2200'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from _____ feet to _____ feet each section.
Plugged off bottom with sand to 3200' and 5 sks. cement. Shot pipe @2400' and 2200'. Pulled up to 750', pumped 10 sks. gel and 50 sks. cement, pulled up to 280', pumped 50 sks. cement, pulled up to 40', pumped 10 sks. cement, topped off with 10 sks. cement, 60/40 pos. 6% gel. Plugging Complete.

RECEIVED

Name of Plugging Contractor Mike's Testing & Salvage, Inc. KANSAS CORPORATION COMMISSION

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rupe Oil Company, Inc. JUL 9 2001

STATE OF Kansas COUNTY OF Rice CONSERVATION DIVISION

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 6th day of July, 2001

[Signature]
 Notary Public

My Commission Expires: _____



OR