

To: 1 030550
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,090-0000
C SE NE, SEC. 25, T 31 S, R 14 ~~W/EX~~
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171
Operator: TXO Production Corp.
Name & Address 155 North Market, Suite 1000
Wichita, KS 67202

Lease Name Mills Feed "C" Well # 1
County Barber 126.75
Well Total Depth 3900 Lansing feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1674

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor FWA Drilling Co., Inc. License Number 6165
Address P. O. Box 850980, Tulsa, OK 73085-0980

Company to plug at: Hour: 7:00 am Day: 15 Month: October Year: 19 85

Plugging proposal received from Allen Dick
(company name) TXO (phone) 316-265-7600

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1674'

- 1st plug at the base of the Anhydrite with 50 sx cement
- 2nd plug 30' below the base of the surface pipe with 40 sx cement
- 3rd plug solid bridge hulls - plug at 40' -- cement to surface with 10 sx cement
- 5th plug to circulate rat hole with 10 sx cement
- 6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:15 am Day: 15 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1330' with 50 sx cement, 2nd plug at 280' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan
(If additional description is necessary, use BACK of this form.)

OCT 28 1985
10-28-85
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

OCT 29 1985

DATE

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 10812

10-15 DEC 16 1985

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 10 7 85 month day year

API Number 15-007-22,090-0000

OPERATOR: License # 5171 Name TXQ Production Corp. Address 155 N. Market Suite 1000 City/State/Zip Wichita, KS 67202 Contact Person Jerry W. Collins Phone 316-265-7600

C SE NE Sec. 25 Twp. 31 S. Rg. 14 East West 3300 660 Ft. from South Line of Section Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 6165 Name FWA Drilling Co., Inc. City/State Yukon, OK 73085

Nearest lease or unit boundary line 660 feet County Barber

Lease Name MILLS FEED 'C' Well # 1

Well Drilled For: Well Class: Type Equipment: Oil SWD Infield X Mud Rotary X Gas Inj X Pool Ext Air Rotary OWWO Expl Wildcat Cable

Ground surface elevation TBD feet MSL

Domestic well within 330 feet: yes X no

Municipal well within one mile: yes X no

Surface pipe by Alternate: 1 X 2

Depth to bottom of fresh water 100

Depth to bottom of usable water 200

Surface pipe planned to be set 250

Projected Total Depth 3800 feet

Formation Lansing

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

cementing will be done immediately upon setting production casing. Date 10-3-85 Signature of Operator Title Drlg. & Production Mgr.

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt.

PUSHER Allen Dick TD 3900 FORMATION Lansing SURFACE PIPE 8 3/8 @ 250 ANHYDRITE ELEVATION 1674 STARTING TIME & DATE COMPLETION TIME & DATE 9:15am 10/15/85 1st PLUG @ 1330 FT. W/ 50 SX 2nd PLUG @ 280 FT. W/ 40 SX 3rd PLUG @ 40 FT. W/ 10 SX 4th PLUG @ FT. W/ SX RAT HOLE CIRCULATION W/ 10 SX MOUSE HOLE CIRCULATION W/ 10 SX WATER SUPPLY WELL PLUGGED W/ SX

60/40 6 9/8 B.J. Titon

RECEIVED STATE CORPORATION COMMISSION OCT 28 1985 10-28-85 CONSERVATION DIVISION Wichita, Kansas