

1 041226

API NUMBER 15-007-21,755-0000

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

SE SE SE, SEC. 24, T 31 S, R 14 W X
330 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5506
Operator: Woolsey Petroleum Corporation
Name & Address: 107 N. Market, Ste. 600
Wichita, KS 67202

Lease Name Mills Feed Well # A-1
County Barber 125.12
Well Total Depth 3850 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 393

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:30 a.m. Day: 16 Month: 12 Year: 19 96

Plugging proposal received from Alan Vratil
(company name) Clarke Corporation (phone) 316-886-5665

Work: 4 1/2" at 3849' w/150 sx cement, PBSD 3835', Perfs at 3772-80'
1st plug sand back to 3722' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 16 Month: 12 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3666' and dump 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2980' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

1 (If ~~you~~ observe this plugging.

DATE 1-3-97

WV. NO. 47262

Signed Steve Pfeifer
(TECHNICIAN)