

2-28

2-040873

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

R

API NUMBER: 15-077-21,138-0000 *NGC KCC*

W/2 E/2 NE ^{SE} NE, SECTION 36 TOWNSHIP 32 RANGE 9W

OPERATOR LICENSE # 5993 2020 FEET FROM S SECTION LINE
OPERATOR KBW OIL & GAS COMPANY 440 FEET FROM E SECTION LINE
NAME & P.O. BOX H
ADDRESS BETHANY, OK 73008
LEASE NAME: KISER #2
COUNTY: HARPER *101.23*
WELL TOTAL DEPTH: 3115'
PIPE: _____
SURFACE CASING: 8 5/8" @ 239'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: CLARK CORPORATION

ADDRESS: MEDICINE LODGE, KS LICENSE: 5105

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: ALAN VITRAL

COMPANY NAME: CLARK CORPORATION PHONE: _____

WERE: PBTD 3087' SAND TO 2720' AND 5 SACKS
5 1/2", 15.5# AT 3113' 35 SACKS AT 1300'
PERF 3050'-3053', CIBP AT 2845', PERF 2777'-2779' 35 SACKS AT 900'
CIRCULATE 290' TO SURFACE

PLUGGING PROPOSAL RECEIVED BY: DISTRICT II

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 10:30 DAY: 28 MONTH: 2 YEAR: 1997


ACTUAL PLUGGING REPORT: THE PERFS WERE COVERED WITH SAND FROM 3113' TO 2695' AND CAPPED WITH 5 SACKS OF CEMENT. 5 1/2" RECOVERED FROM 1950' AND PULLED FROM WELLBORE. TUBING RAN TO 1307', 35 SACK PLUG. TUBING PULLED TO 871', 35 SACK PLUG. TUBING PULLED TO 280', CEMENT CIRCULATED TO SURFACE. TUBING PULLED AND CEMENT TOPPED OFF.

REMARKS: 60/40 POZ 4% GEL ALLIED CEMENT

INVOICED

DATE 3-10-97
WIL NO. 47710
2-28

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 10 1997
3-10-97
CONSERVATION DIVISION
WICHITA, KS

I DID OBSERVE THIS PLUGGING.

STEVE VAN GIESON