

2 040518

12-1

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 077-21,122-0000

NE SE, SEC. 36, T 32 S, R 8W (W)E

1980 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5993

Lease Name Kiser Well # 1

Operator: KBW Oil & Gas

County Harper 122.04

Name: P. O. Box H

Well Total Depth 3755 feet

Address: Bethany, OK 73008

Conductor Pipe: Size feet

Surface Casing: Size 8-5/8 feet 262

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Medicine Lodge, KS

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Elmo Morganstien

(company name) Clarke Corporation (phone)

were: PBD 2839' - sand to 2730' & 4 sx - 35 sx @ 1400' - 35 sx @ 900' - 85 sx

@ 300' - squeezed @ 2745' - bridge plug 2874'

4-1/2" 3754' - perms 3659-63', 2782-83.5'

RECEIVED  
STATE CORPORATION COMMISSION

DEC 19 1989

12-19-89

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 13:11 Day: 1 Month: 12 Year: 1989

ACTUAL PLUGGING REPORT The perms were sanded to 2730' & capped w/4 sx cmt -

4-1/2" was recovered from 2440' and pulled to 1380' & 35 sx cmt spotted - 4-1/2"

pulled to 880' & 35 sx cmt spotted - 4-1/2" pulled to 260' and cmt was circ

to surface.

Remarks: B.J. Titan #573191 60/40 poz 2% gel

INVOICED

(If additional description is necessary, use BACK of this form.)

I (did xxxxxx) observe this plugging.

DATE 1-5-90

Signed

(TECHNICIAN)

INV. NO. 26891

12-1