

To: 1 040619
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-5 API NUMBER 15- NA 007-21035-0000 54
NE SE NW, SEC. 8, T. 31 S, R. 14 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 30481

3630 feet from S section line
2970 feet from E section line
Lease Name Stucky Well # 1

Operator: Apollo Energies, Inc.
Name & Address 405 Commodore
Pratt, KS 67124

County Barber 150.31
Well Total Depth 4625 feet

Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 820

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104-0187

Company to plug at: Hour: 1:15 p.m. Day: 5 Month: 2 Year: 19 92

Plugging proposal received from Jim Byers
(company name) Apollo Energies, Inc. (phone) 316-672-7324

Work: 4 1/2" at 4625' w/150 sx cement, PBD 4614', Perfs at 4602-10, 4582-86, 4399-4406'
1st plug sand back to 4349' and dump 4 sx cement on top of sand bridge through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"
wiper plug and dump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 2 p.m. Day: 5 Month: 2 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4349' and dumped 4 sx cement on top of sand
bridge through bailer.
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Maximum pressure 800 psi and shut in 300 psi.

MAR 11 1992
CONS. DIVISION
WICHITA, KANSAS
2-11-92

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3500' of 4 1/2" casing.
(Additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE: MAR 10 1992
WELL NO. 34701
2-5

Signed Steve Pfeifer
(TECHNICIAN)

MAY 19 1992 OCT 28 1992