

15-007-10180-0000

1 010121

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 11-23-48

SW SE NW, SEC. 17, T 31 S, R 14 W 1/4
2970 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5061

Lease Name Skinner B Well # 2

Operator: Robert F. White
Name & Address: 505 Union Center
Wichita, KS 67202

County Barber 137.25
Well Total Depth 4423' feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 852

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:30 pm Day: 27 Month: March Year: 19 86

Plugging proposal received from Roger Lust

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4406' Open Hole
1st plug sand back to 4350' and dump 5 sx cement on top of sand through bailer.
2nd plug squeeze well with 3 sx hulls, 10 sx gel, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:15 pm Day: 27 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 1200 psi and shut in 700 psi

APR - 7 1986
4-7-86
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 3000' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Joel Durrant (TECHNICIAN)

DATE APR 8 1986
INV. NO. 13344