

1080211

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,807-0000

C NE NW, SEC. 29, T 31 S, R 14 W
4620 feet from N SE Corner of section line
3300 feet from W SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Jacobs "M" Well # 1

Operator: TXO Production Corp.
Name & Address: 200 West Douglas, Suite 300
Wichita, KS 67202

County Barber

Well Total Depth 3975 129.19 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 327

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Buling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8:30 pm Day: 11 Month: September Year: 19 84

Plugging proposal received from Norman Voth

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 2661' PBDT 2620' Perfs 2461-68'

1st plug pump 35 sx cement and stopped plug at 2200'

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 pm Day: 11 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 2661' PBDT 2620' Perfs 2461-68'

1st plug pumped 35 sx cement and stopped plug at 2200', 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 100 sx cement.

RECEIVED STATE CORPORATION COMMISSION

SEP 24 1984 9-24-84

CONSERVATION DIVISION Wichita, Kansas

Maximum pressure 650 psi and shut in pressure 500 psi

Remarks: They recovered 1685' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Sun.

(if additional description is necessary, use BACK of this form.)

(If desired, observe this plugging.)

Signed J. H. Metz (TECHNICIAN)

DATE 10-1-84 INV. NO. 3933