

1 010011

API NUMBER 15- 007-21,788-~~0000~~

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NW NE, SEC. 29, T 31 S, R 14 W/8
4545 feet from S section line
1935 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Jacobs "K" Well # 1

Operator: TXO Production Corp.
Name & Address 200 West Douglas, Suite 300
Wichita, KS 67202

County Barber 138.13
Well Total Depth 4250 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 346 ✓

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:00 am Day: 29 Month: July Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 4249' PBD 3850' Perfs at 2885-92'

1st plug sand back to 2835' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 20 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Robert B. Tarbutton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 am Day: 29 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 2835' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 20 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 400 psi

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE _____

INV. NO. 9439

RECEIVED signed STATE CORPORATION COMMISSION

AUG 2 1985 8-2-85

[Signature]
(TECHNICIAN)