

1 050932

8-28-87

2151R

API NUMBER 15- 007-22,088-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NE SW SE, SEC. 14, T 33 S, R 11 W/E

990 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4538

Lease Name Circle Well # 1-14

Operator: Boswell Energy Corporation

County Barber

Name & Address 6001 N. Robinson,

Well Total Depth 4625 feet

Oklahoma City, OK 73118

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Wilson Casing Pulling License Number 3158

Address P.O. Box 963, Woodward, OK 73802

Company to plug at: Hour: 11 a.m. Day: 28 Month: 8 Year: 19 87

Plugging proposal received from Sid Wilson

(company name) Wilson Casing Pulling (phone) 405-256-6023

were: 4 1/2" at 4625' PBD 4610' Perfs at 4505-25' Elevation 1490'

1st plug pump 4 sx hulls and 20 sx cement,

2nd plug pump 50 sx cement at 600',

3rd plug pump 40 sx cement at 270',

4th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15 p.m. Day: 28 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 4 sx hulls and 20 sx cement to 4450',

2nd plug pumped 50 sx cement at 630',

3rd plug pumped 40 sx cement at 270,

4th plug pumped 10 sx cement at 40'.

RECEIVED STATE CORPORATION COMMISSION

Remarks: Used Class H cement by Halliburton. Recovered 3401' of 4 1/2" casing. SEP 1 1987

(If additional description is necessary, use BACK of this form.) IN DIVISION Wichita, Kansas

INVOICED

DATE 9-4-87

Signed Richard W. Lucas (TECHNICIAN)

INV. NO. 18031 8-28