

1
050484

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,471-00-00

W/2 NE SE, SEC. 31, T 33 S, R 11 W/EX

1980 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Lease Name Newkirk Well # 2

Operator: Edmiston Oil Company
Name & Address 1260 Kansas State Bank Building
Wichita, KS 67202

County Barber 152.75

Well Total Depth 4700 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 246 ✓

Abandoned Oil Well ☒ Gas Well ☒ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2:00 pm Day: 25 Month: March Year: 19 85

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4699' PBTD 4689' Perfs at 4606-4624'

1st plug sand back to 4556' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls
and 125 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 3:00 pm Day: 25 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4556' and dumped 4 sx cement on top of
sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement,
10 sx gel, 1 sack hulls and 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 04 1985

Maximum pressure 700 psi and shut in 600 psi

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 3500' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Sun.

(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 4-9-85
INV. NO. 7525

observe this plugging.

Signed Richard M. Lacey
(TECHNICIAN)