

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD

Barber County, Sec. 13 Twp. 33 Rge. 12 (E) (W)X

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner Okmar Oil Co.

Lease Name Groendycke B Well No. #1

Office Address 970 Fourth Financial Center Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 8-7-75 19

Plugging completed 8-11-75 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation Depth to top Bottom Total Depth of Well 4463'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Contains data for 5 1/2" and 8 5/8" casing.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3500'. Mixed and ran 5 sacks cement thru dump bailer. Mudded hole to 290' to set 10' rock bridge. Plug well with 5 yards ready-mix concrete to base of cellar.

RECEIVED STATE CORPORATION COMMISSION

AUG 13 1975

Name of Plugging Contractor Southwest Casing Pulling Co. (If additional description is necessary, use BACK of this sheet)

Address Box 364 Great Bend, Kansas 67530

CONSERVATION DIVISION WICHITA, KANSAS

STATE OF Kansas COUNTY OF Barton

Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec

Box 364 Great Bend, Kansas

(Address)

Subscribed and sworn to before me this 12 day of August 19 75

Sidney D. Miller Notary Public



DRILLERS LOG

GROENDYKE B NO. 1

CASING RECORD:	OPERATOR:	Okmar Oil Co.	DESCRIPTION:
8-5/8" @430'	CONTRACTOR:	Sage Drilling Co	NE NE SW
w/350 sax cement	COMMENCED:	August 21, 1973	Sec. 13-33S-12W
TOTAL DEPTH:	COMPLETED:	September 3, 1973	Barber County, Kansas
4463'			ELEVATION: 1413KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Red Bed	0	131	
Red Bed & Shale	131	438	
Shale & Red Bed	438	470	
Shale	470	1029	
Shale	1029	1550	
Lime and Shale	1550	1815	
Shale	1815	1950	
Lime and Shale	1950	2135	
Lime and Shale	2135	2336	
Lime and Shale	2336	2565	
Lime and Shale	2565	2760	
Lime and Shale	2760	2925	
Lime	2925	3100	
Lime and Shale	3100	3240	
Lime and Shale	3240	3418	
Lime and Shale	3418	3585	
Lime and Sahel	3585	3600	
Lime	3600	3727	
Lime	3727	3730	
Lime and Shale	3730	3938	
Lime	3938	3969	
Lime	3969	4070	
Lime and Shale	4070	4160	
Lime	4160	4263	
Lime	4263	4345	
Lime and Shale	4345	4413	
Lime	4413	4440	
Lime and Chert	4440	4448	
Lime	4448	4463	

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1975

CONSERVATION DIVISION
Wichita, Kansas

5 1/2" @4462'
w/275 sax cement

I certify that this is a true and correct copy of the above log to the best of my knowledge

SAGE DRILLING CO., INC.

By Clarence Michael
Clarence Michael

Subscribed and sworn to before me this 7th day of September, 1973.

Donna J. Highhill
Donna J Highhill, Notary Public

My commission expires:
April 20, 1977