

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-007-21697-00-00

API NUMBER _____
LEASE NAME Groendyke
WELL NUMBER #1
SPOT LOCATION 100SW-NE-NE-SW
SEC. 13 TWP. 33S RGE. 12 ~~XX~~ XX or (W)
COUNTY Barber
Date Well Completed 11-21-83
Plugging Commenced 12-31-83
Plugging Completed 2-7-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Hummon Oil Company
ADDRESS Suite 400 - One Main Place - Wichita, KS 67202

PHONE # () _____ OPERATORS LICENSE NO. 5050

Character of Well Dry
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Paul Luthi

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 3830

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	223	None
				5 1/2	3737	3000

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Plugged back at 3708. Sand from 3708 to 3575.

5 sacks cement from 3575 to 3540. Sun Cementing pumped off top. Pumped in 3 hulls - 10 jell - 50 Cement - 10 jell - 1 hull. Plugged.
100 sacks cement. 60-40 POZ. 2% 3%.

Metz and Zimmerman on location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105
Address P O Box 187 - Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Barber, ss.

Elmo Morgenstern

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed that the same are true and correct, so help me God.

(Signature) Elmo Morgenstern
(Address) Medicine Lodge, KS 67104

RECEIVED
FEB 13 1984

STATE CORPORATION COMMISSION
Wichita, Kansas

Subscribed and sworn to before me this 10 day of February, 1984

Lamela Ricketts
Notary Public

My Commission expires: 10-11-87

DRILLERS LOG


#1 Groendycke

CASING RECORD:	COMPANY:	Hummon Corporation	DESCRIPTION:
8-5/8" @ 223' w/215 sx. cement	CONTRACTOR:	Big-H Drilling, Inc.	100'SW/NE NE SW Sec. 13-33S-12W Barber County, KS
5-1/2" @ 3737' w/100 sx. cement	COMMENCED:	November 14, 1983	ELEV: 1427 KB
	COMPLETED:	November 21, 1983	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Red Beds	0	228	
Shale	228	585	
Red Beds & Shale	585	1378	
Shale & Lime	1378	3830	
RTD		3830	

I certify that this is a true and correct copy of the above log to the best of my knowledge.


BIG-H DRILLING, INC.



Karen Tennis

Subscribed and sworn to before me this 5th day of December, 1983.

SANDRA L. MENDOZA
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY APPT. EXP. 2/13/86



Notary Public

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1983
CONSERVATION DIVISION
Wichita, Kansas