

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barber SEC. 13 TWP. 33S RGE. 12W E/W
Location as in quarters or footage from lines:
C of SW NE

Locate Well
correctly on above
Section Platt.

Lease Owner Edmiston Oil Co., Inc.
Lease Name Harbaugh B-2 Well No.
Office Address 800 Vickers/KSB&T Bldg., Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole):
Date Well Completed
Application for plugging filed
Plugging commenced 4/1/81
Plugging completed 4/15/81
Reason for abandonment of well or producing formation

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation Depth to top bottom T.D. 3696

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	321	None
				4-1/2"	3666	3294

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Made bottom hole plug back with sand to 3550. Mixed and ran 4 sacks cement thru dump baler. Pulled 18" tension. Made shots at 3340 and 3275. Pulled total string of 102 joints. Squeezed hole with 15 sacks gel, 6 sacks hulls and 10 sacks gel. Released plug and displaced with 125 sacks 50/50 pos 4% gel 3% cc. Plugging complete.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso

Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of April, 19 81

My Commission expires:



JOAN KELSO
State of Kansas
My Appt. Exp. Oct. 15, 1984

Joan Kelso
Notary Public.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado, Derby Bldg.
Wichita, Kansas 67202

INVOICE and WELL PLUGGING AUTHORITY

May 28, 1981

5467-W

INVOICE NUMBER: _____

TO: Edmiston Oil Company]
800 Vickers KSB&T Bldg.
Wichita, KS, 67202

PLUGGING ASSESSMENT AS FOLLOWS:

Harbaugh "B"-2

C SW NE, Sec13-33S-12W

Barber

\$120.12

Kelso Casing Pulli ng

NOTE: We also need the following before our file is completed:

 x Well Plugging Record (CP-4)
 x Well Log
 x Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.

PAYABLE UPON RECEIPT

For Administrator

Mr. Maurice Leslie, R. R. #1, Nashville, KS., 67112

is hereby assigned to supervise the plugging of the above mentioned well.