

15-007-00402-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit

Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 21 Twp. 30S Rge. (E) 14 (W)  
Location as "NE/CNW/SW" or footage from lines NE NE NW  
Lease Owner Sterling Drilling Company, et al  
Lease Name Baker Well No. 1  
Office Address Sterling, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 19 19 57  
Application for plugging filed November 19 19 57  
Application for plugging approved November 19 19 57  
Plugging commenced November 19 19 57  
Plugging completed November 19 19 57  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4700 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8"	200'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud. Bottom plug set @ 195' with (1/2 sack hulls and Halliburton 13 3/8" plug) with 30 sacks cement. Filled hole with heavy mud to 30' and set Halliburton plug and 1/2 sack hulls with 15 sacks cement poured in hole to bottom of cellar.

STATE CORPORATION COMMISSION  
11-27-57  
NOV 27 1957  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Group Exploration Company  
Address Sterling, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.  
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner  
F. A. Wuellner  
Sterling, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of November, 1957  
Bernard Laudermilk Notary Public.  
My Commission Expires Jan. 22, 1958

PLUGGING  
FILE SEC 21 T 30 R 14 W  
BOOK PAGE 62 LINE 39

GROUP EXPLORATION COMPANY  
Sterling, Kansas

WELL LOG ----- BAKER #1 -----  
Located: NE NE NW, Section 21-30S-11W, Barber County, Kansas

OWNER: Sterling Drilling Company, et al  
ROTARY DRILLING CONTRACTOR: Group Exploration Company

COMMENCED: 10-28-57  
COMPLETED: 11-19-57

TOTAL DEPTH: 4700'

LOG

0 - 60	Sand
60 - 100	Red Bed
100 - 200	Red Bed & Gyp Rock
200 - 340	Red Bed & Shale
340 - 635	Red Bed, Shale & Shells
635 - 785	Red Bed
785 - 800	Anhydrite
800 - 930	Red Bed, & Shale
930 - 975	Salt
975 - 1100	Salt & Red Bed
1100 - 2005	Shale
2005 - 2970	Lime
2970 - 3030	Shale
3030 - 3305	Shale & Lime
3305 - 3770	Lime
3770 - 3875	Lime & Shale
3875 - 3940	Sand & Shale
3940 - 4020	Shale & Lime
4020 - 4475	Lime
4475 - 4515	Lime & Chert
4515 - 4550	Lime
4550 - 4570	Viola Lime & Chert
4570 - 4573	Lime & Sand
4573 - 4585	Simpson
4585 - 4593	Sand
4593 - 4620	Simpson Sand
4620 - 4635	Simpson, Shale & Chert
4635 - 4670	Sand & Shale
4670 - 4680	Shale & Lime
4680 - 4700	Arbuckle T. D.

CASING RECORD

Set 13-3/8" surface casing @ 200'  
with 225 sacks cement, 2% c.c.

**RECEIVED**  
STATE CORPORATION COMMISSION

NOV 27 1957  
~~11-27-57~~  
CONSERVATION DIVISION  
Wichita, Kansas

PRODUCTION

Plugged & Abandoned

<b>PLUGGING</b>	
FILE	SEC 21 T 30 R 14W
BOOK	PAGE 62 LIT 39