


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barber County, Sec. 21 Twp. 30S Rge. (E) 14 (W)
Location as "NE/CNW/SW" or footage from lines C SW NE
Lease Owner Glickman Oil Co.
Lease Name Pickens Well No. 1
Office Address P. O. Box 11104 - Wichita, Kansas 67211
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Jan. 12, 1969
Application for plugging filed Jan. 28, 1969
Application for plugging approved (by phone) Jan. 12, 1969
Plugging commenced Jan. 12, 1969
Plugging completed Jan. 12, 1969
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4014 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	206'	10-3/4"	206'	None
		0	980'	8-5/8"	980'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 300'. Set first plug @ 300' w/1/2 sack hulls and 25 sacks cement. Filled hole with heavy mud to 40'. Set second plug @ 40' w/1/2 sack hulls and 10 sacks cement. Plugged rat hole w/2 sacks cement. Job completed @ 8:00 PM, 1-12-69.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place - Wichita, Kansas 67202


STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. E. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall

830 Sutton Place - Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of January, 1969

Barbara J. Layton
Barbara J. Layton, Notary Public.



15-007-20084-0000

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
STATE CORPORATION COMMISSION
JAN 31 1969
CONSERVATION DIVISION
Wichita, Kansas

PICKENS #1
C SW NE Section 21-30S-14W
Barber County, Kansas

Commenced: December 30, 1968
Completed: January 12, 1969

OPERATOR - Glickman Oil Co.

DEPTH	FORMATION	REMARKS
From	To	
0	206	Sand and red bed Ran 6 joints 10-3/4" casing, set @ 206' w/275 sacks cement.
206	425	Sand and red bed
425	880	Red bed
880	980	Red bed and shells Ran 26 joints 8-5/8" casing, set @ 980' w/125 sacks cement.
980	1065	Red bed and shells
1065	1575	Shale and shells
1575	2603	Lime and shale
2603	2735	Shale
2735	4014	Shale and lime
4014	TD	Dry and abandoned.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C SW NE Section 21-30S-14W, Barber County, Kansas to the best of my knowledge and belief.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 28th day of January, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972

Barbara J. Layton
Barbara J. Layton, Notary Public

