

15-007-00479-0008

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Barber

County. Sec. 23 Twp. 30 Rge. 14 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SE SE

Lease Owner National Cooperative Refinery Association

Lease Name Lambert Well No. 1

Office Address 820 Union National Bank Building

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 15, 19 52


Application for plugging filed December 15, 19 52

Application for plugging approved December 16, 19 52

Plugging commenced December 16, 19 52

Plugging completed December 16, 19 52

Reason for abandonment of well or producing formation Non Productive



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4750 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	961	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole from 4750' to 300' with heavy mud, set plug. Dumped 20 sacks cement thru drill pipe. Judded hole to 35', set plug, dumped 10 sacks cement on up to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation

Address 1516 Liberty Bank Building, Oklahoma City, Oklahoma.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

W. Jean La Coss (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) W. Jean La Coss

820 Union National Bank Building (Address)

SUBSCRIBED AND SWORN TO before me this 17 day of December, 19 52

My commission expires February 20, 1953

24-2675-S 2-52-20M

PLUGGING
FILE SEC 23 TWP 30 R 14
BOOK PAGE 66 LINE 17

RECEIVED
STATE CORPORATION COMMISSION

DEC 18 1952
12-18-52
CONSERVATION DIVISION
Wichita, Kansas

Notary Public.

NATIONAL COOPERATIVE REFINERY ASSN.LAMBERT #1NE 1/4 SE 1/4 SE 1/4 Section 23-30-11W

Barber County, Kansas.

<u>FORMATIONS</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	0	100	
Sand and gravel	100	127	
Sand	127	130	
Red Bed and shells	130	285	
Shale and shells red bed	285	341	
Red Rock	341	430	
Red Rock and shale	430	750	
Red Bed	750	855	
Gray Shale	855	925	
Shale	925	935	
Anhydrite	935	955	
Red Bed	955	1050	8-5/8" C.S.A. @ 948.74'. Cemented with 650 sacks cement.
Grey Shale and Red Shale	1050	1300	
Shale and shells	1300	1835	
Shale and lime	1835	1920	
Sandy Lime	1920	2060	
Lime	2060	2260	
Lime and shale	2260	2340	
Lime	2340	2435	
Shale and lime	2435	2515	
Lime and shale	2515	2575	
Shale	2575	2620	
Lime and shale	2620	2675	
Shale and shells	2675	2810	
Shale and lime	2810	3070	
Lime	3070	3115	
Shale and lime	3115	3295	
Lime	3295	3435	
Lime and shale	3435	3763	
Shale and lime	3763	3833	
Sand - Lime	3833	3842	
Lime and shale	3842	4082	
Lime	4082	4387	
Lime and chert	4387	4426	
Cherty, Conglomerate	4426	4443	
Lime and chert	4443	4487	
Lime and shale	4487	4527	
Lime - Viola	4527	4555	
Chert & Lime	4555	4575	
Chert	4575	4591	
Shale and chert	4591	4602	
Shale and lime	4602	4624	
Sandy shale	4624	4638	
Shale and sand	4638	4661	
Shale and lime	4661	4692	
Sand and shale	4692	4700	
Arb. lime	4700	4728	

PLUGGING
 FILE SEC 23-30-11W
 BOOK PAGE 66 LINE 17

RECEIVED
 THE CORPORATION COMMISSION
 DECEMBER 1952
 12-23-52
 DIVISION

15-007-00479-0000

FORMATION

FROM TO

Line

4728 4750

Total Depth

4750

I hereby certify the foregoing to be a true and accurate Driller's Log of the formations encountered in the above well.

TRANSIT CORPORATION

BY

L. J. Kruse

L. J. Kruse, Assistant Secretary

Subscribed and sworn to before me this 19th day of December, 1952

Betty Ben Garvin

Betty Ben Garvin, Notary Public.

My commission expires September 25, 1956.

12-23-52