


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barbara County, Sec. 24 Twp. 30S Rge. 14 (E) 14 (W)
Location as "NE/CNWSW" or footage from lines. C NE 1/2 NW 1/2
Lease Owner Pickrell Drilling Company
Lease Name Shriver Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 25, 1962
Application for plugging filed March 25, 1962
Application for plugging approved March 25, 1962
Plugging commenced March 25, 1962
Plugging completed March 25, 1962
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4822 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8"	215'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 200'. Set Plug.
Cemented with 30 sacks cement.
Heavy mud to 35'. Set Plug.
Cemented with 10 sacks cement
to bottom of cellar. Plugged
rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 4 1962
4-4-62
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
C. W. Sebitts

(Employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of April, 1962

My commission expires September 24, 1962

Maxine Johnson
Maxine Johnson
Notary Public.



15-007-00099-0000
ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita 2, Kansas

LOCATION: Shriver #1 - C NE 1/4 NW 1/4
Barber County, Kansas

Rotary Drilling Commenced 3-10-62

Rotary Drilling Completed 3-25-62

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: 215' (6jts) 13 3/8" Spiralweld casing cemented w/200 sacks cement.
Circulated. Completed at 4:30 AM. No oil string run. D & A

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

		<u>Circulated for Samples</u>	
125'	Sand	4413'	4740'
820'	Red Bed	4495'	4761'
845'	Anhydrite	4505'	4795'
1050'	Red Bed	4525'	4822'
1680'	Shale - Shells	4615'	
1750'	Salt, Shale - Shells	4720'	
2110'	Shale - Shells		
2285'	Lime & Shale		
2660'	Lime		
2965'	Lime & Shale		
3120'	Shale & Shells		
3480'	Lime & Shale		
3675'	Lime		
3878'	Lime & Shale		
3940'	Lime, Sand & Shale		
4030'	Lime & Shale		
4390'	Lime		
4472'	Lime & Shale		
4500'	Lime & Chert		
4720'	Chert & Dolemite		
4745'	Simpson		
4761'	Lime, Shale & Sand		
4795'	Shale		
4822'	Arbuckle R.T.D.		

Slope Test

1500' 0°
2500' 0°
3500' 10°
4500' 0°

S. L. M.

3225'
3859'
4254'

RECEIVED
STATE CORPORATION COMMISSION
APR 4 1962
4-4-62
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 2nd day of April, 1962, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: September 24, 1962

Maxine Johnson
Maxine Johnson Notary Public