

OPERATOR

15-135-22327-0000

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR Gear Petroleum Co., Inc. LEASE Bowman 1-28

SEC 28 TWP 20S RGE 22W

FILL IN WELL LOG AS REQUIRED:

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand-Shale	-0-	375	Anhydrite	1408
Shale	375	850	Heebner	3686
Sand	850	1060	LKC	3736
Shale	1060	1406	Base LKC	4069
Anhydrite	1406	1441	Ft. Scott	4256
Shale & Shells	1441	1600	Mississippi	4360
Shale	1600	2230		
Shale & Lime	2230	4015		
Lime	4015	4365		
RTD		4365.		
<p>DST #1, 4257-80, Times 30/30/60/60                      Rec. 430' OGCM, 300' Water,                      Flow P 102/173-234/357,                      SIP 1335/1325</p> <p>DST #2, 4303-65, Times 30/30/60/60                      Rec. 2400' O&amp;OCM, 1050' water,                      Flow P 459/1255-1345/1375                      BHP 1375/1384</p>				

RELEASED

DEC 10 1983

FROM CONFIDENTIAL

*Rec'd 1-21-83*

Report of all strings set— surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	24 lb	486'	Common	275	2% gel. 3% cc.
Production	7-7/8"	4 1/2"	10 1/2 lb	4360'	Common	100	10% salt.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			None		

TUBING RECORD

Size	Setting depth	Packer set at
2 7/8	4360	None

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

Date of first production 1/8/1983	Producing method (flowing, pumping, gas lift, etc.) Pumping	Gravity 36° API
--------------------------------------	--	--------------------

RATE OF PRODUCTION PER 24 HOURS	Oil 40 bbls.	Gas TSTM MCF	Water 43 %	Gas-oil ratio ----- CFPB
---------------------------------	-----------------	-----------------	---------------	-----------------------------

Disposition of gas (vented, used on lease or sold) Used on lease

Perforations Open hole 4360-65