

To: 1 052163 9-2  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License / \_\_\_\_\_

Operator: Kansas Corporation Commission  
Name: \_\_\_\_\_  
Address 130 S. Market, Rm. 2078  
Wichita, KS 67202

API NUMBER 15- 007-20,141-00-01  
C NE NW, SEC. 29, T. 30 S, R. 14 W/E  
4620 feet from S section line  
3300 feet from E section line  
Lease Name Mills Well # 1-29 OWWO

County Barber  
Well Total Depth 4515 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 13 3/8 feet 205

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11 a.m. Day: 2 Month: 9 Year: 19 97

Plugging proposal received from Richard Lacey

(company name) KCC (phone) 316-338-1610

logs: 5 1/2" at 4512' w/100 sx cement, Perfs at 4376-79', Est. TOC 4000', PBTD 4180'

1st plug sand back to 4300' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls, release 13 3/8" wiper plug and pump 150 sx cement.

RECEIVED  
KANSAS CORP COM  
SEP 19 97  
26-9-97

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:15 p.m. Day: 2 Month: 9 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug on 8/26/97, sanded back to 4000' and dumped 5 sx cement on top  
of sand bridge through bailer,

2nd plug pumped down 13 3/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 200 lbs. hulls, and 150 sx cement.  
Maximum pressure 450 psi and ISIP 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did / ~~XXXXXX~~) observe this plugging.

Signed Richard M. Lacey  
(TECHNICIAN)