

1 120064

135-00311-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 8-20-64

C NW NW , SEC. 24 , T 20 S, R 22 (W) EXX

4620 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

Lease Name Bondurant Well # A-1

Operator: Rains & Williamson Oil Co.

County Ness 142.68

Name & Address 435 Page Court Building

Well Total Depth 4390 feet

220 West Douglas,

Conductor Pipe: Size feet

Wichita, KS 67202

Surface Casing: Size 8 5/8 feet 255

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rains & Williamson Oil Co. License Number 5146

Address 435 Page Court Building, 220 West Douglas, Wichita, KS 67202

Company to plug at: Hour: 10:25 am Day: 2 Month: May Year: 19 86

Plugging proposal received from Jerry Ptachek

(company name) Rains & Williamson (phone) 316-265-9686

were: 5 1/2" at 4385' Open Hole 4385-90' Squeezed (1978) 3414-3449' with 200 sx

100' Squeezed (1980) Depth unknown with 200 sx, Squeezed 3038' with 150 sx, and squeezed

(1985) at 2914' with 300 sx cement.

Squeeze with 1 sack hulls and fill 5 1/2" with econolite

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 am Day: 2 Month: May Year: 19 86

ACTUAL PLUGGING REPORT Squeezed well with 1 sack hulls and 235 sx cement - Maximum

pressure 900 psi and shut in 150 psi. Hooked to 8 5/8" x 5 1/2" casing annulus. Pumped

in 15 sx at 50 psi. Rathole broke out - flowed 2 - 3 B cement to pit.

RECEIVED STATE CORPORATION COMMISSION MAY 12 1986 CONSERVATION DIVISION Wichita, Kansas

Remarks: No recovery. Used 65/35 Pozmix 10% gel 2% A-2 (Econolite) by BJ-Titan

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE MAY 12 1986

Signed Dan C. Uebel (TECHNICIAN)

INV. NO. 13769