

1 050710

DOCKET No. D-20,136 R

API NUMBER 15- 135-21,935-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NE NW, SEC. 20, T 20 S, R 22 W/4
4624 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5205

Lease Name Barricklow Well # 3

Operator: Mid-Continent Energy Corporation
Name & Address: 120 South Market, Suite 310
Wichita, KS 67202

County Ness 158.60
Well Total Depth 4880 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 531

Abandoned Oil Well Gas Well Input Well SWD Well X D&A
Other well as hereinafter indicated

Plugging Contractor Mid-Continent Energy Corporation License Number 5205
Address 120 South Market, Suite 310, Wichita, KS 67202

Company to plug at: Hour: 10:30 am Day: 5 Month: December Year: 19 85

Plugging proposal received from Pete Musgrove
(company name) Mid-Continent (phone) 316-265-9501

were: 4 1/2" at 4785' Open Hole 1 1/2 joints of 2 3/8" tubing and packer left on bottom of hole
Pump down 4 1/2" with 1 sack hulls, 50 sx cement, 15 sx gel, 4 1/2" plug and 130 sx cement.
Pump down 8 5/8" & 4 1/2" annulus with 5 sx gel, 175 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:30 pm Day: 5 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" with 1 sack hulls, 50 sx cement, 15 sx gel, 4 1/2" plug and 130 sx cement. 2nd plug pumped down 8 5/8" - 4 1/2" annulus with 5 sx gel and 175 sx cement.

Maximum pressure on 4 1/2" 250 psi and shut in 250 psi

Maximum pressure on 8 5/8" 500 psi and shut in 400 psi

Remarks: No Recovery. Used 60/40 Pozmix 6% gel by BJ-Titan
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 16 1985
INV. NO. 11528
12-5

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1985
12-10-85
CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacey
(TECHNICIAN)