

1 070717

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-21,671-0000
C NW NW, SEC. 20, T. 20 S, R 22 W/EX

TECHNICIAN'S PLUGGING REPORT

4620 feet from S section line
4620 feet from E section line

Operator License # 5205

Lease Name Barricklow Well # 1

Operator: Mid-Continent Energy Corporation
Name & Address 155 North Market, Suite 200
Wichita, KS 67202

County Ness 144.95

Well Total Depth 4460 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 490

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pluggers Inc. License Number 3909

Address P.O. Box 782050, Wichita, KS 67278

Company to plug at: Hour: 3:45 p.m. Day: 18 Month: 8 Year: 19 89

Plugging proposal received from Ron Hoover

(company name) Pluggers Inc. (phone) 316-733-2770

were: 4 1/2" at 4460' Perfs at 4350-52'

1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 13 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 p.m. Day: 18 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 4 sx cement on top of
sand through bailer.

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 13 sx gel, 100 lbs. hulls,
and 150 sx cement down 8 5/8".

Maximum pressure 1200 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2128' of 4 1/2" casing.
(If additional description of well is necessary, use BACK of this form.)

INVOICED

DATE 8-28-89

NO. 25741

8-18

OCT 04 1989

RECEIVED
MUG 25 1989
8-25-89
Signed _____
CONSERVATION DIVISION
Wichita, Kansas

Dan Johnson
(TECHNICIAN)

NOV 06 1989