

1 040393

1-10 15-007-20192-00-00

143

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19- Drill Completion Date 11/3/71

C/S/2 SW, SEC. 12, T. 33 S, R. 12 W/E

660 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245

Lease Name Harbaugh Well # 1

Operator: Okmar Oil Company

County Barber

Name & Address Box 723

Well Total Depth 4455 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 244

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:30 a.m. Day: 10 Month: 1 Year: 19 90

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 3881' Perfs at 3403-07, 3410-12, 3414-17'

1st plug sand back to 3350' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 10 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3350' and dumped 5 sx cement on top of sand with dump bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement,

Maximum pressure 550 psi and shut in 500 psi.

STATE CORPORATION COMMISSION

JAN 18 1990

Remarks: Used 60/40 Pozmix 2% gel by B.J. Titan. Recovered 2500' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (If you wish to observe this plugging.)

DATE JAN 29 1990

Signed Stephen J. Pfeiffer
(TECHNICIAN)

INV. NO. 27221