

To: 1 090801 4-6
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 007-22,533-00-00
SE NW NW, SEC. 12, T 33 S, R 12 W/E
4290 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 31532
Operator: Bison Production Co.
Name & Address: 9320 E. Central
Wichita, KS 67206

Lease Name Prothe Well # 1-12
County Barber 142.84
Well Total Depth 4395 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Co. License Number 5929
Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: _____ Day: 6 Month: 4 Year: 19 97

Plugging proposal received from Sally
(company name) Duke Drilling Co. (phone) 316-267-1331

to fill hole with heavy mud and spot cement through drill pipe Anhydrite 600'

1st plug at 600' with 50 sx cement, 2nd plug at 290' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:30 a.m. Day: 6 Month: 4 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 600' with 50 sx cement,

2nd plug at 290' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE 4-11-97

WV. NO. 47907

4-6 JUN 17 1997

Signed 
(TECHNICIAN)

RECEIVED
KANSAS DORP COMM
1997 APR 10 A 11:01