

To: 1041121
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 007-20,190-00-00
C W/2 W/2, SEC. 12, T 33 S, R 12 W/E
2640 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5363
Operator: BEREXCO INC.
Name & Address: P.O. Box 723
Hays, KS 67601

Lease Name Warren Well # 1
County Barber 144.40
Well Total Depth 4443 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 245

Abandoned Oil Well _____ Gas Well x Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor BEREXCO INC. License Number 5363
Address P.O. Box 723, Hays, KS 67601

Company to plug at: Hour: 11 a.m. Day: 16 Month: 11 Year: 19 95
Plugging proposal received from George Jorgenson
(company name) BEREXCO INC. (phone) 913-628-6101

Perfs: 5 1/2" at 4442' w/250 sx cement, PBSD 4405', Perfs at 3752-4390' (7 sets)
Squeezed perfs from 3398-3432' (3 sets)

1st plug pump 3 sx hulls, 30 sx cement, gel spacer, and cement from 600-0',
2nd plug pump 100 sx cement down tubing/casing annulus:

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____
Operations Completed: Hour: 12 p.m. Day: 16 Month: 11 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" casing with 300 lbs. hulls and 30 sx cement, (Class A)
followed with gel spacer up to 600' from surface followed by 50 sx 65/35 Pozmix 6% gel.

Back to surface maximum pressure 100 psi and shut in 0 psi.
2nd plug pumped down 5 1/2" X 8 5/8" annulus with 100 sx 65/35 Pozmix 6% gel.
Maximum pressure 300 psi and shut in 200 psi.

RECEIVED
STATE CORPORATION COMMISSION
Wichita, Kansas

NOV 21 1995

Remarks: Used 65/35 Pozmix 6% gel, Class A cement by Applied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOLVED
DATE NOV 27 1995
INV. NO. 44119

Signed Stephen Pfeifer
(TECHNICIAN)