

338
R

To: 1010080
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,695-00-00

N/2 NE SW, SEC. 1, T 33 S, R 11 (W) ~~11~~

2310 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8572

Lease Name Schiff Well # 2

Operator: The Reach Group
Name & Address 229 E. William, Suite 500

County Barber 149.99

Well Total Depth 4615 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 292

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling Service License Number 6497

Address P. O. Box F, Sublette, KS 67877

Company to plug at: Hour: 11:45 am Day: 27 Month: January Year: 19 86

Plugging proposal received from Ed Eves

(company name) Midwest (phone) 316-675-8349

were: 4 1/2" at 4614' PBD 4600' Perfs at 4542-4548' Pump through 4 1/2" with mud between plugs

1st plug pump 2 sx hulls and 20 sx cement to bottom and stop plug at 4140'

2nd plug at 900' with 50 sx cement

3rd plug at 330' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:20 pm Day: 27 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx cement to 4120', 2nd plug at 900' with 50 sx cement and 5 sx gel, 3rd plug at 330' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 0 and shut in pressure 0

ECR 4 1986

Remarks: Recovered 3530' 5 1/2" casing. Used common cement by Midwest. (if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE FEB 6 1986

INV. NO. 12419

1-27

Signed 
(TECHNICIAN)