

1041404

TG: STATE CORPORATION COMMISSION

API NUMBER 15-007-22,611-00-00  
SW/4 SEC. 3, T 33 S, R 11 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2970 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME INSLEE WELL # 1

TECHNICIAN'S PLUGGING REPORT 6/30 COUNTY BARBER 148.53

OPERATOR LICENSE # 8061 WELL TOTAL DEPTH 4570 FEET

OPERATOR: OIL PRODUCERS INC OF KS PRODUCTION CSG: SIZE 4 1/2" @ 4569' WITH 100 SX

NAME AND PO BOX 8647 SURFACE CASING: SIZE 8 5/8" @ 237' WITH 150 SX

ADDRESS WICHITA, KS 67208

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 EAST BETH DR. STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 1:15 PM DAY: 30 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCNTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 4449-4455 & 4463-4517

SANDED BACK TO 4389' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER. LOAD HOLE

WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 600' WITH 50 SX CEMENT.

2ND PLUG AT 260' WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 2:15 PM DAY: 30 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT

SANDED BACK TO 4389' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER. LOAD HOLE

WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 600' WITH 50 SX CEMENT. RECEIVED

2ND PLUG AT 260' WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT. STATE CORPORATION COMMISSION

JUN 14 2000

CONSERVATION DIVISION  
Wichita, Kansas

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3054' OF 4 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED  
DATE 2/18/00 SIGNED  
WV. NO. 1060076

Stephen J. Pfeifer  
(TECHNICIAN) FORM CP-2/3