

To: **1040917**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5255

Operator: McGinness Oil Company
Name & Address: 150 N. Main, Ste. 1026
Wichita, KS 67202

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A ☒ X

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____

Address P.O. Box 368, Medicine Lodge, KS

Company to plug at: Hour: 10 a.m. Day: 18 Month: 11 Year: 19 94

Plugging proposal received from Doug McGinness

(company name) McGinness Oil Company (phone) 316-267-6065

Notes: 5 1/2" at 14516' w/125' sx cement, PBTD 2850', BP at 3660', Perf seat 3632-35, 3585-88'
2900' (squeezed), 2803-08'

Well was previously plugged on 10/2/87. The 5 1/2" casing was perforated at 750' and 333 sx of cement was circulated from 750-0'.

1st plug pump down 5 1/2" casing with 200 lbs. hulls and 235 sx cement.

Check annulus. _____ Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ X Part _____ None _____

Operations Completed: Hour: 10:45 a.m. Day: 18 Month: 11 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" casing with 200 lbs. hulls and 235 sx cement.

Maximum pressure 1200 psi and shut in 700 psi.

Tied onto 5 1/2" X 8 5/8" annulus and pressured to 1000#. Held.

Remarks: Used 60/40 Pozmix 6% gel by Allied. 5 1/2" cemented in to surface.
(If additional description is necessary, use BACK of this form.)

I (did/ did not) observe this plugging.

DATE 12-6-94

INV. NO. 41824
11-18 FEB 16 1995

API NUMBER 15- 007-01,043-00-01

C SW SW, SEC. 3, T 33 S, R 11 W/E

660 feet from S section line

4620 feet from E section line

Lease Name Inslee "OWWO" Well # 1-A

County Barber 119.60

Well Total Depth 3680 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 280

STATE RECEIVED
NOV 23 1994

CONSERVATION DIVISION
WICHITA, KANSAS

Signed Stephen J. Pfeifer

(TECHNICIAN)