

7-13-88

1 040137

API NUMBER 15- 007-01.014-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW NE, SEC. 9, T 33 S, R 12 W/EX
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4419
Operator: Bear Petroleum
Name & Address: P.O. Box 107
Haysville, KS 67060

Lease Name Bower Well # 1
County Barber 162.99
Well Total Depth 5015 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 316

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 1:15 p.m. Day: 13 Month: 7 Year: 1988

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 4991' Perfs at 4882-92' Elevation 1533'KB

1st plug sand back to 4830' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:45 p.m. Day: 13 Month: 7 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4830' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, and 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 10 1988

Maximum pressure 800 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3040' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (void XXXXXX) observe this plugging.

DATE 7-26-88

INV. NO. 21645-7-13

Signed Stephen J. Pfeifer (TECHNICIAN)

SEP 12 1988