

101405

TO: STATE CORPORATION COMMISSION

API NUMBER 15-007-22-544-00-00
C-NW-SW SEC. 9, T 33 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 2050 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 820 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME BOGGS WELL # 4-9

TECHNICIAN'S PLUGGING REPORT 4/6 COUNTY BARBER 160.65

OPERATOR LICENSE # 31088 WELL TOTAL DEPTH 4943 FEET

OPERATOR: COLT RESOURCES CORP. PRODUCTION CSG: SIZE 5 1/2" @ 4924' WITH 175 SX

NAME AND 16701 GREENS POINT PARK DR. SURFACE CASING: SIZE 8 5/8" @ 210' WITH 150 SX

ADDRESS HUSTON TEXAS 77060

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 BETH DRIVE, STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 06 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: CIBP @ 4770 PERFS @ 4676-4704

PUMPED DOWN 5.5" CASING WITH 500 #'S OF HULLS FOLLOWED WITH 30 SX. COMMON CEMENT PUMP

PLUGS THRU CASING 1ST PLUG AT 600' WITH 10 SX GEL - 50 SX CEMENT. 2ND PLUG AT 240' WITH 50

SX. CEMENT 3RD. PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 3:01 PM DAY: 06 MONTH: 04 YEAR: 2000

ACTUAL PLUGGING REPORT PUMPED 5 1/2 W/ 500#S HULLS & 30SX. COMMON CEMENT

PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 600' WITH 10 SX GEL - 50 SX

CEMENT. 2ND PLUG AT 240' WITH 50 SX

CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED CEMENTINGR RECOVERED 2835' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

RECEIVED
STATE CORPORATION COMMISSION

SIGNED

Stephen J. Pfeifer
(TECHNICIAN) FORM CP-2/3

JUL 14 2000

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 7/18/00

WV. NO. 1060081

(Handwritten initials and stamps)