

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

10-2

API NUMBER: 15-077-21,292-0000
NE, SW, SECTION 1 TOWNSHIP 31 RANGE 5W

OPERATOR LICENSE # 5038 1980 FEET FROM S SECTION LINE
3300 FEET FROM E SECTION LINE

OPERATOR ROBINSON OIL COMPANY
NAME & 300 W. DOUGLAS, ST. #420
ADDRESS WICHITA, KS 67202

LEASE NAME: HART "A" #1
COUNTY: HP Harper
WELL TOTAL DEPTH: 3820 124.15

PIPE: NONE

SURFACE CASING: 8 5/8" @ 300'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: DUKE DRILLING

ADDRESS: WHICITA, KS LICENSE: 5929

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: JOHN ARMBRUSTER

COMPANY NAME: DUKE DRILLING PHONE: 316-

WERE: 35 SX. @ 1000', 35 SX. @ 550', 35 SX. @ 350', 25 SX. @ 60', 15 SX. IN RATHOLE.

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { }

COMPLETED: HOUR: 7:00 DAY: 2 MONTH: 10 YEAR: 1995

ACTUAL PLUGGING REPORT:

THE DRILL PIPE WAS RUN OPEN END TO 1000' WHERE 35 SX. OF CMT. WAS SPOTTED. THE DRILL PIPE WAS PULLED TO 550', WHERE 35 SX. OF CMT. WAS SPOTTED. DRILL PIPE PULLED TO 350', 35 SX. WAS SPOTTED. DRILL PIPE PULLED TO 60', 25 SX. CMT. SPOTTED. DRILL PIPE RUN IN RATHOLE & CIRCULATED WITH 15 SX. CMT.

REMARKS: ALLIED CMT. 60/40 POZ. 4% GEL.
I DIDNOT OBSERVE THIS PLUGGING.

Steve Van Gieson
Steve Van Gieson (AGENT)

FORM CP-2/3
REV. 3/90

RECEIVED
KANSAS CORPORATION COMMISSION

INVOICED

DATE DEC 06 1995

INV. NO. 44227

DEC 06 1995

12-6-95
CONSERVATION DIVISION
WICHITA, KS