

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-21088-00-06<sup>01</sup>  
Spot: SENW Sec/Twnshp/Rge: 28-20S-22W  
3300 feet from S Section Line, 3300 feet from E Section Line  
Lease/Unit Name: BOWMAN Well Number: 1  
County: NESS Total Vertical Depth: 4355 feet

Operator License No.: 31142 Conductor Pipe: Size \_\_\_\_\_ feet:  
Op Name: PETROLEUM PROPERTY SERVICES, INC Surface Casing: Size 8.625 feet: 469 WITH 250 SX CMT  
Address: 155 N. MARKET, STE 1010 Production: Size 5.5 feet: 4350 WITH 150 SX CMT 141.54  
WICHITA, KS 67202 Liner: Size \_\_\_\_\_ feet:

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/19/2001 9:20 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: LEON KUHN Company: PPSI Phone: (785) 483-2022

Proposed Plugging Method: RUN TUBING TO 4300' & PUMP 60 SX CMT & 300# HULLS. PULL TO 1500' AND CIRCULATE CMT. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 04/19/2001 11:45 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4345'. CIBP @ 4345'. PERFS AT 4258-63' / 2 STAGED AT 1440' WITH 325 SX CMT. CIRCULATED. RUN TUBING TO 4300' AND PUMPED 60 SX CMT WITH 300# HULLS. PULLED TO 1500' AND PUMPED 130 SX CMT. CIRCULATED. PULLED TUBING AND TOPPED OFF WITH 25 SX CMT. STAYED FULL. WENT DOWN BACKSIDE AND PUMPED 5 SX CMT. PRESSURED TO 500# AND HELD.

INVOICED

DATE 4-26-01

INV. NO. 2001061717

RECEIVED  
STATE CORPORATION COMMISSION

LDR 26 2001  
4-26-01  
CONSERVATION DIVISION

Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed

Michael Maier  
(TECHNICIAN)

APR 25 2001

Form CP-273