

1 050599

API NUMBER 15-135-20,946-0600

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 150'S C SW SW SEC. 27, T 20 S, R 22
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

510 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Mary "B" Well # 1

Operator: Gear Petroleum Co., Inc.

County Ness 140.99

Name & Address 300 Sutton Place

Well Total Depth 4338 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 406

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____

Address Box 31, Russell, KS 67665

Company to plug at: Hour: 10:00 am Day: 13 Month: August Year: 1985

Plugging proposal received from Butch Hoberecht

(company name) Gear (phone) 316-793-8803

were: 5 1/2" at 4331' PBD 4320' Perfs at 4232-38' Stage Collar at 1382' circulated with 325 sx cement.

Squeeze well with 1 sack hulls, 25 sx cement, 24 sx gel, release 5 1/2" plug and pump 115 sx cement

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00 noon Day: 13 Month: August Year: 1985

ACTUAL PLUGGING REPORT Squeezed well with 1 sack hulls, 25 sx cement, 16 sx gel, released 5 1/2" plug and pumped 80 sx cement, 8 sx gel and 40 sx cement.

Maximum pressure 2000 psi and shut in 1300 psi

Remarks: No recovery. Used 60/40 Pozmix 6% gel by Allied. (If additional description is necessary, use BACK of this form.) R.W.S.

INVOICED

DATE 8-20-85

INV. NO. 9687

AUG 20 1985

Signed Richard W. Lacy (TECHNICIAN)