

To: 1 120923
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200th COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-18

API NUMBER 15- 135-21,871-0916
N/2 NE SW, SEC. 28, T. 20 S, R. 22 W/X
2310 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8247

Operator: Robert F. Hembree
Name & Address: P.O. Box 458
Ness City, KS 67560

Lease Name McFadden Well # 1

County Ness

Well Total Depth 4353 141.47 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 483

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hembree Well Service Inc. License Number 6907

Address P.O. Box 458, Ness City, KS 67560

Company to plug at: Hour: 2 p.m. Day: 17 Month: 5 Year: 19 94

Plugging proposal received from Fred Hembree

(company name) Hembree Well Service (phone) 913-798-3408

vers: 5 1/2" at 4350' w/150 sx cement, PBD 4320', Perfs at 4260-63'

1st plug pump 100lbs. hulls and 25 sx cement, displace w/water to 4000';

2nd plug perforate at 700', pump 150 sx cement down 5 1/2".

If no returns, pump 150 sx cement down 8 5/8" X 5 1/2".

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 18 Month: 5 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug set CIBP in 5 1/2" casing,

2nd plug perforate 5 1/2" casing at 700', pump in 5 1/2" casing with 200 sx cement, lost circulation at 200 sx.

3rd plug pumped in 8 5/8" X 5 1/2" annulus with 50 sx cement. Pumping pressure 300 psi and shut in pressure 600 psi.

135 sx cement went out perfs at 700' and up the hole.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

If additional description is necessary, use BACK of this form.

I (did / ~~did not~~) observe this plugging.

DATE 6-7-94

WV. NO. 40542

5-18

Signed Dean Rucker
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

JUN 07 1994

CONSERVATION DIVISION
Wichita, Kansas