

15-135-20972-0000

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

JAN 20 1975  
1-20-75  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Mack Oil Company

Complete Address P. O. Box 400, Duncan, Oklahoma 73533

Lease Name Cook Well No. 1

Location C SE SE Sec. 28 Twp. 20 Rge. (E) (W) 22

County Ness ~~Franklin~~ ~~McCurtain~~ Total Depth 4420'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Russ Casing Pulling

Address Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 3:45 P Day 16 Month 1 Year 1975

The above well was plugged as follows:

Total Depth 4420' 8 5/8 csg 360' cwc 250 sk.

4 1/2 csg set 4401' cw 100 sk cem.

4 1/2 csg PBSD 4331' & perf. (4304-4318)

Filled 4 1/2 csg with sand (4331-4200) dumped 4 sk cmt W/dump bailer. (4200-4170)

Cutoff & recovered 2410' of 4 1/2 csg.

Pulled 4 1/2 csg to 25' -squeezed down 8 5/8 csg thru 4 1/2 swage with 25 sk gel & water -  
200 lbs hulls & 115 sk 60-90 poz cement by HOWCO. PP 600 lbs. SIP 400 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Waring  
Well Plugging Supervisor

INVOICED

DATE 1/22/75

INV. NO. 681-W