

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

FORM CP-3  
Rev. 6-4-68

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 30 1980  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Ks. 67202

API Number 15 -135-21009-0000 (of this well)

Operator's Full Name ROCKWOOD PETROLEUM COMPANY.  
 Complete Address 815 DOUGLAS, BLDG. - WICHITA, KANS. 67202  
 Lease Name MARY Well No. "B" #3  
 Location SE-SW Sec. 27 Twp. 20 Rge. 22 (E) (W) W  
 County NESS Total Depth 4349 EL  
 Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
 Other well as hereafter indicated \_\_\_\_\_  
 Plugging Contractor HALLIBURTON SERVICES  
 Address EAST HWY 40 - HAYS, KANS. License No. \_\_\_\_\_  
 Operation Completed: Hour 2:40 Day 29 Month OCT Year 1980

The Above well was plugged as follows:

8 5/8" 440' SP. CMT. @ 250' CMT. → 5 1/2" SET AT 4343' 275' CMT.  
SQUEEZED @ 1401' @ 325' CMT. CIRCULATED TO SURFACE.  
PERF'S - OPEN HOLE 6' - NO PIPE RECOVERY.  
ORDERED 140' 5/50 Permox 6% GEL. → 25' GEL. - 2' HULLS. + 5 1/2" PLUG.  
PUMPED IN 8 5/8" WITH PUMP TRUCK.  
PUT IN 1' HULLS - 50' CMT. → 25' GEL. - RELEASED PLUG.  
AND 90' CMT. - MAX PRESSURE 1600 LB

INVOICED

CEMENTED BY HALLIBURTON CMT.

I hereby certify that the above well was plugged as herein stated.

DATE 11-4-80

INV. NO. 3527-W

Signed: W. J. Schmidt  
Well Plugging Supervisor

W E L L L O G

OPERATOR: O. A. SUTTON 15135-21009-0000  
 WELL NAME: MARY "B" #3 LOCATION: C SE SW SEC 27-20S-22W  
 COUNTY: NESS STATE: KANSAS  
 WELL COMMENCED: FEB 16, 1975 WELL COMPLETED: MARCH 1, 1975  
 ELEVATION: 2174 KB TOTAL DEPTH: 4349'  
 PRODUCTION: PRODUCING RIG NO: 1

CASING - 8-5/8": SET @ 440.09' (11 JTS) 8 5/8" NEW 20# SURFACE CASING  
 W/250 SX COMMON / 2% GEL / 3% CA CL  
 5-1/2": RAN 4351.15' (125 JTS) 5 1/2" 14# CASING. SET 5' OFF  
 BOTTOM @ 4343' W/150 SX HALLIBURTON LITE / 125 SX  
 SALT SAT POZMIX-2 STAGED 1401' TO SURFACE  
 ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	835	SHALE & RED BED	3/4° @ 1219'	
835	1045	SAND		
1045	1371	RED BED		
1371	1423	ANHYDRITE		
1423	1950	SHALE		
1950	2000	LIME & SHALE		
2000	2060	SHALE & SHELLS		
2060	3905	LIME & SHALE		
3905	4345	LIME		
4345	4349	MISSISSIPPI		
	4349	RTD		

DST #1 4330'-4345'  
 OPEN 30 SI 45 OPEN 120 SI 45  
 WEAK BLOW. RECOVERED 40'  
 FREE OIL, 20' MUDDY OIL,  
 60' OCM,  
 IBHP 1394# FBHP 1374#  
 IFP 31# FFP 82#  
 DST #2 4330'-4349'  
 OPEN 30 SI 45 OPEN 90 SI 45  
 REC 640' OIL, 60' OIL CUT WATER  
 IBHP 1364# FBHP 1314#  
 IFP 41# FFP 329#

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 27 1980  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 COUNTY OF SEDGWICK ) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Jay H. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, This 5th day of March, 1975.

MY COMM. EXP. DEC. 7, 1975

Phyllis Buchanan  
 PHYLLIS BUCHANAN - NOTARY PUBLIC

