

15-135-19160-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 9 1964
11-9-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Rains & Williamson

Complete Address: 1425 Wichita Plaza Wichita, Kans

Lease Name Goatley Well No. 1

Location CNE NE Sec. 23 Twp. 20 Rge. (E) (W) 22

County Ness Total Depth 4383

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor:

Address: License No.

Operation Completed: Hour 11:45 Day 2 Month 11 Year 64

The Above well was plugged as follows:

8 5/8" 325' circulated with cement.

Circulated hole with heavy mud, set plug at 540' - displaced 20 sax cement through drill pipe, heavy mud to 300', set plug and displaced 20 sax cement through drill pipe, heavy mud to 40', set plug, 1/2 sack hulls and filled to bottom cellar with cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/9/64

INV. NO. 119-W

Signed: Edson Petty
Well Plugging Supervisor