

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-4-68

RECEIVED
STATE CORPORATION COMMISSION

MAR 22 1978

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -135 -21,432 -0000 (of this well)

Operator's Full Name Abercrombie Drilling Inc.
Complete Address 801 Union Center, Wichita, Kansas
Lease Name Torney Well No. 1
Location C SW SW Sec. 22 Twp. 20 Rge. (E) (W) 22
County Ness Total Depth 4415'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor T-Bird Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 7:45 A Day 13 Month 3 Year 1978

The above well was plugged as follows:

RTD 4415' 8 5/8 csg set 359' cwc Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3-23-78

INV. NO. 6982-3

Signed: Leo Messing
Well Plugging Supervisor