

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-135-00350 0000

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 15 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mull Drg Co
Complete Address: 1625 Wichita Plaza Wichita, Kansas
Lease Name Emery Well No. 1
Location CNW NW Sec. 19 Twp. 20 Rge. (E) (W) 22
County Ness Total Depth 4460
Abandoned Oil Well Gas Well Input Well SWD Well D & A x
Other well as hereafter indicated:
Plugging Contractor: Same & Globe Cementing Co
Address: Great Bend, Kans License No.
Operation Completed: Hour 1:30PM Day 8 Month 1 Year 64

The Above well was plugged as follows:

8 5/8" 209' circulated with cement.

Circulated hole with heavy mud, set plug at 500', displaced 20 sax
cement through drill pipe at 500', heavy mud to 200', set plug and
displaced 20 sax cement through drill pipe, heavy mud to 40', set
plug, hulls and filled to bottom cellar with cement.

Cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 1/15/64

INV. NO. 8465-W