

W
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 29 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Jones & Gebert Oil Co.

Complete Address: 205 Central Bldg., Wichita, Kansas

Lease Name Hindman Well No. # 1

Location C SE NE Sec. 11 Twp. 33 Rge. 12 (E) (W) W

County Barber Total Depth 4474

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Ralph Comstock Pipe Pulling

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 11:00AM Day 25th Month July Year 1963

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cement circulated. 4474' of 4 1/2" long string,
cemented with 125 sacks. Plugged back to 4437'. Top perferation 4411'.
Sanded to 4400', cemented with 3 sacks. Fluid level was up in hole.
Plug was pushed to 250', 10' rock bridge, mixed 5 sacks cement and put
on plug through dumpbailer, and let set over night. Next morning hole
was bailed down, and 15 sacks added to plug. Hole was filled with mud to
40', 10' rock bridge, cemented with 10 sacks to base cellar.
3208' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/29/63

INV. NO. 7478-W