

15-135-21011-C000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAY 9 1975
5-9-75
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Rains & Williamson Oil
Complete Address 435 Page Court, Wichita, Kansas
Lease Name Bondurant "C" Well No. 1
Location 150° N of C SW NW Sec. 24 Twp. 20 Rge. (E) (W) 22
County Ness Total Depth 4410'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 12:15 P Day 5 Month 5 Year 1975

The above well was plugged as follows:

RTD 4410' 8 5/8 csg set 297' cwc 175 sx. Flg. Mat. 50-50 poz 2% total gel.
Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.
Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Murray
Well Plugging Supervisor

INVOICED

DATE 5/12/75
INV. NO. 1310-w