

KANSAS
STATE CORPORATION COMMISSION
RECEIVED
CONSERVATION DIVISION AGENT'S REPORT CORPORATION COMMISSION

APR 13 1967

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Well Plugging Authority,
issued April 3, 1967.

Operator's Full Name Mobil Oil Corporation

Complete Address: Box 1828, Oklahoma City, Oklahoma

Lease Name Riley MacGregor Well No. # 1

Location SE Sec. 5 Twp. 33 Rge. 11 (E) (W) W

County Barber Total Depth 4480'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 11:45AM Day 10th Month April Year 1967

The Above well was plugged as follows:

363' of 9 5/8" surface pipe, cemented with 350 sacks. 3782' of 5 1/2" long
string, cemented with 150 sacks. Plug back T.D. 3751'. Top perferation
3658'. Bottom of the hole was sanded to 3600', and cemented with 5 sacks,
through the dump bailer. 3000' of 5 1/2" long string was recovered from the
hole. Fluid level in the hole was at 300', bridge plug and rock bridge
from 300' to 290', and cemented with 25 sacks. Hole was filled with mud
to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 4/13/67
INV. NO. 5050-W

Signed: Archie Eling
Well Plugging Supervisor