

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasIntent to Drill,
filed March 22, 1967.Operator's Full Name Sioux Petroleum CompanyComplete Address: Drawer 270, Medicine Lodge, KansasLease Name Drum "A" Well No. # 1Location App. C SW SW Sec. 6 Twp. 33 Rge. 11 (E) (W) WCounty Barber Total Depth 3600'Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Hellar Drilling Company, Inc.Address: 1014 Union Center Bldg., Wichita, Kansas License No. _____Operation Completed: Hour 11:00AM Day 29th Month March Year 1967

The Above well was plugged as follows:

215' of 8 5/8" surface pipe, cement circulated with 210 sacks. Hole
was filled with drilling mud to 200', 1st cementing plug, bridged with
2 sacks of dry cement and 1/2 sack of hulls on fluid at 200', and cemented
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at
40', and cemented with 9 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

MAR 31 1967

Signed: Archie Elving
Well Plugging SupervisorCONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 3/31/67
INV. NO. 4983-W