

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
OCT 19 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Socony Mobil Oil Company, Inc.

Complete Address: 300 North Broadway, Wichita, Kansas

Lease Name Boggs Estate Well No. # 1

Location C SW SW SW Sec. 9 Twp. 33 Rge. 12 (E) (W) W

County Barber Total Depth 4891'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Company

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 10:30AM Day 18th Month Oct. Year 1965

The Above well was plugged as follows:

1715' of 8 5/8" surface pipe, cemented with 800 sacks. 4862' of 5 1/2"
string, cemented with 250 sacks. Plug back to 4442'. Top perferation
4427'. Bottom of the hole was sanded to 4400', and cemented with 5
sacks. 3600' of 5 1/2" long string was recovered from the hole. Hole was
filled with mud to 300', rock bridge from 300' to 290', and cemented
with 25 sacks. Hole was filled with mud to 40', rock bridge from 40'
to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED
DATE 10/20/65
INV. NO. 2014-W