

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Champlin Oil & Refining Co.

Complete Address: P. O. Box 308, Ellinwood, Kansas

Lease Name Brass Well No. # 1

Location C NW SW Sec. 4 Twp. 33 Rge. 15 (E) (W) W

County Barber Total Depth 5260

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractors: Ace Pipe Pulling Co.

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 11:30AM Day 15th Month Nov. Year 1963

The Above well was plugged as follows:

277' of 8 5/8" surface pipe, cemented with 215 sacks. 5222' of 5 1/2" long
string, cemented with 110 sacks. Plug back to 4830'. Top perferation 4758'.
Bottom of hole was sanded to 4740', and cemented with 5 sacks. Fluid was
bailed down. Plug was set at 270', with 10' rock bridge, cemented with
25 sacks. Hole was filled with mud to 40', 10' rock bridge, cemented
with 10 sacks to base cellar.
4320' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

DATE 11/18/63
INV. NO. 8123-W

Signed: Archie Elving
Well Plugging Supervisor