

KANSAS

al
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 4 - 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Beren Corporation

Complete Address 1130 Vickers KSB&T Bldg. Wichita, Ks

Lease Name Lendon D Well No. 1

Location SW/NW/SW Sec. 5 Twp. 33 Rge. 15 (E) (W) W

County Barber Total Depth 5010

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Co. Inc.

Address Box 364 Great Bend, Ks License No. 399

Operation Completed: Hour 2:00 PM Day 2 Month 5 Year 1972

The above well was plugged as follows:

230 ft 13 3/8 surface pipe cement circulated. 5000 ft 5 1/2 long string
cemented with 175 sacks. Top perf. 4700 ft. Sand back to 4550 ft,
5 sacks cement with bailer. Pulled 4034 ft 5 1/2. Set 10 ft rock
bridge at 180 ft. Fill hole with 6 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed *[Signature]*
Well Plugging Supervisor

INVOICED

DATE 5/8/72
INV. NO. 5683-w