

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 27 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Bulldog Pipe & Supply Company

Complete Address: 311 Mayo Bldg., Tulsa, Oklahoma

Lease Name Long Well No. # 1

Location C SW SW Sec. 24 Twp. 33 Rge. 12 (E) (W) W

County Barber Total Depth 4630'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Clarke Corporation, Inc.

Address: Chapin Bldg., Medicine Lodge, Kansas License No. 583

Operation Completed: Hour 12:30PM Day 23rd Month Dec. Year 1966

The Above well was plugged as follows:

355' of 8 5/8" surface pipe, cement circulated. 4628' of 5 1/2" long string,
cemented with 150 sacks. Top perferation 4514'. Bottom of the hole was
sanded to 4500', and cemented with 8 sacks, through the dump bailer.
3925' of 5 1/2" long string was recovered from the hole. Fluid in the hole
was bailed down to 300', bridge plug and rock bridge from 300' to 290',
and cemented with 25 sacks. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 12/27/66

INV. NO. 45 27-W