


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 7 Twp. 33 Rge. 10 (E) (W) X  
Location as "NE/CNWxSWx" or footage from lines Center of SW NE  
Lease Owner E. K. Edmiston  
Lease Name Traffas Well No. 1  
Office Address 501 First National Building Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 12-14-64 19  
Application for plugging approved 12-15-64 19  
Plugging commenced 12-15-64 19  
Plugging completed 12-30-64 19  
Reason for abandonment of well or producing formation  
Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving  
Producing formation Depth to top Bottom Total Depth of Well 4687 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUR IN	PULLED OUT
				8 5/8	210	None
				4 1/2	None	3825

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded to 4640'. Dumped 4 sacks of cement.  
Cleaning out cellar.  
Rigging up jacks. Working pipe.  
Working pipe. Shot pipe at 4200' - 4100' - 4000' - 3900' & 3800'.  
Mudded to 3000'.  
Working pipe. Circulating. Spotted 75 bbl of oil.  
Working pipe.  
Working pipe. Pulling pipe.  
Pulling pipe. Plugging well. Bailed water. Build rock bridge at 240'. Dumped 25 sacks of cement. Filled hole and rock bridge.  
Capped well with 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 8 1965  
01-08-1965  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
I, O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6 day of January, 1965

My commission expires May 27, 1965 Notary Public.

15-007-30151-00-00

DRILLER'S LOG

Company: E. K. Edmiston  
 501 First National Bank Building  
 Wichita, Kansas 67202

Rotary Drilling Commenced: August 6, 1964

Rotary Drilling Completed: August 20, 1964

Well Name: TRAFFAS No. 1  
 C SW/4 NE/4 7-33S-10W  
 Barber County, Kansas

Contractor: E. K. Edmiston Drilling Co., Inc.  
 501 First National Bank Building  
 Wichita, Kansas 67202

Casing Record: 240' of 8-5/8" with 175 sacks cement  
 4730' of 4-1/2" with 125 sacks cement

L O G

Measurements from top of Rotary Bushing

Clay and Post Rock	0 - 50
Shale	240
Shale and Shells	1385
Shale and Lime	1765
Lime	2060
Lime and Shale	2225
Lime	2370
Lime and Shale	3667
Shale and Lime	3869
Sand	3944
Lime and Shale Breaks	3990
Lime	4130
Lime and Shale Breaks	4199
Shale and Lime	4267
Lime	4465
Lime and Shale Breaks	4508
Lime	4629
Lime and Shale Breaks	4659
Lime	4730 RTD

RECEIVED  
STATE CORPORATION COMMISSION

JAN 19 1965  
01-19-1965  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, E. K. EDMISTON, President of E. K. Edmiston Drilling Co., Inc., hereby certifies, on behalf of said company, that the above log is a true and correct log of the formations encountered in drilling the above well, as reflected by the daily drilling reports.

E. K. EDMISTON DRILLING CO., INC.

By 

STATE OF KANSAS,  
SS:  
SEDGWICK COUNTY,

BE IT REMEMBERED that on this 24th day of August, 1964, before me, the undersigned, a Notary Public within and for the county and state aforesaid came E. K. EDMISTON, known to me to be the same person who executed the foregoing instrument and duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

My commission expires  
August 25, 1964

  
A. B. Bargaen, Notary Public

